

NTC ferme pentru Noiembrie 2015: licitatii lunare_V1

Luand in considerare :

- Programe de retrageri in SEN si SE interconectate;
- Generatie initiala in CHE Portile de Fier si Djerdap **1140 MW** (700 MW + 440 MW) ; CEE 1200MW+CEF 300MW;
- Limita pe LEA400kV Portile de Fier-Djerdap **1600 A** (TC Portile de Fier) ;
- Export initial RO **700MW**, BG **800MW**
- Import initial GR+MK+AL+TR+HR **2590MW** (+200MW export IT pe cablu GR-IT) , export initial RS **36MW**, import initial HU **2450MW**
- Masuri preventive si post-avarie. Schimburi prognozate; fara soldare; conventii bilaterale.

Valorile NTC fiabile pe granitele Romaniei in **Noiembrie 2015** pentru licitatii lunare sunt :

NTC	01.11	02-06.11	07-08.11	09-11.11	12-13.11	14-15.11	16-17.11	18-26.11	27-29.11	30.11	
	Rahman-Dobrudja		Isaccea-Rahman								
		BucS-SI	BucS-Pelic	Tantareni-Urechesti							
		Sm-Gut	AT Urech.	Smird-Gut					BS-D		
		Paro-BaruM	Arad-Timisoara								
	Mukacevo-V.Kapusany						Tiszalok-Muk / Kisvardia-Muk				
	Bekescsaba-Szolnok										
		Kosovo-Urosevac		Sokolnice-Krizovany							
		Varna-Burg	CMogila-Vetren								
RO=>HU	650										
HU=>RO	700										
RO =>RS	500										
RS =>RO	800										
a											
RO =>BG	400										
BG =>RO	400										
RO=>UA	50										
UA =>RO	50	100		150	200						
ROexport	1600										
ROimport	1950	2000		2050	2100						

a
a
a
a
a
a

- TRM export/import in interfata RO **300MW / 400MW**; Suma TRM export pe granite cu BG, RS, HU;
- In regimuri post-avarie: LEA 220kV Portile de Fier-Resita-Timisoara 1,2 $\leq I$ termic 20° & 120%TC ; AT Rosiori $\leq 105\%$; LEA 110kV $\leq 100\%$ (20°C);
- Valori NTC calculate functie de limita de incarcare inainte de **actiunea automatizatorilor P pe LEA 220kV Portile de Fier-Resita 1,2** ;
- Masuri preventive / postavarie: - Conditionari de regim (iarna 2015-2016);
- Masuri dispecerizare productie (*)
- - modificare preventiva/postavarie a ploturilor AT400/220kV Arad, AT400/220kV Urechesti;
- - descarcare/deconectare a unor grupuri in CHE Portile de Fier I post-avarie;
- - conectarea post-avarie a T Oradea in rezerva (**2TO**), AT 400/220kV Mintia in rezerva (**2ATM**), a CT 110kV Iernut (**CI**);
- - conectarea preventiva LEA 110kV Varadia-C.Surduc (**VrS**); deconectarea preventiva LEA 110kV Arad-CET Arad (**#L**)

TTC ferme pentru Noiembrie 2015: licitatii lunare_V1

Valorile TTC fiabile pe granitele Romaniei in **Noiembrie 2015** pentru licitatii lunare sunt :

NTC	01.11	02-06.11	07-08.11	09-11.11	12-13.11	14-15.11	16-17.11	18-26.11	27-29.11	30.11
RO=>HU	750									
HU=>RO	800									
RO =>RS	600									
RS =>RO	900									
RO =>BG	500									
BG =>RO	500									
RO=>UA	150									
UA =>RO	150		200	250	300					
ROexport	1900									
ROimport	2350		2400	2450	2500					

- TRM export/import in interfata RO **300MW / 400 MW**;
- TRM export/import pe granita 100MW;
- **TTC export total in interfata RO # Suma TTC export pe granite:**
TRM export in interfata de interconexiune RO = suma TRM export pe granite cu BG, RS, HU.