

NTC pentru Aprilie 2012 _V3z :

Luand in considerare :

- Programe de retrageri in SEN si SE interconectate;
- Generatie initiala in CHE Portile de Fier si Djerdap 1800MW (900MW +900MW);
- Limita pe L400kV Portile de Fier-Djerdap 1600 A (PdFier); reglaje de iarna la protectii in Serbia ;
- Automatici de putere pe LEA 220kV Portile de Fier-Resita deconectate;
- Import initial GR+MK+AL 1100MW, Turcia 50MW, HU 1065MW, RS 190MW.;
- Export initial RO 600MW, BG 400 MW
- Masuri preventive si post-event. Schimburi prognozate; fara soldare; conventii bilaterale.
- [Amanarea retragerii simultane a LEA 220kV Arad-Timisoara si Arad-Calea Aradului in mai 2012.](#)

Valorile NTC fiabile pe granitele Romaniei in **Aprilie 2012**, cu reevaluarea perioadei 02-08, sunt :

NTC	01.04 2012	02-06.04 2012	07-08.04 2012	09-12.04 2012	13-15.04 2012	16-20.04 2012	21-22.04 2012	23-26.04 2012	27-29.04 2012	30.04 2012
	Arad-Timis.	+ Arad-CArad				Arad-Safa	Tant.-Urec.			AT2 A.Iulia
	Brasov-Gutin.					Domn.-Brazi	Stejaru-Gheo.			
	Burst.-Muk.				Isaccea-Rahm					
	Beograd-Obr.							Beogr-Obr.		BaiaM-Tihau
		Albert.-ZUkr.						AT1 Timis		AT1 Timis.
RO=>HU	400									
HU=>RO	300						350			
RO =>RS	600				650					
RS =>RO	300									
RO =>BG	300	350	300							
BG =>RO	250	300	250					200		
RO=>UA	50									
UA =>RO	100									
RO Export	1350	1400	1350		1400					
RO Import	950	1000	950			1000		950		

- TRM export/import in interfata RO **300 MW / 400 MW**
- TRM export in interfata RO+BG **300 MW**

Limite

Export :

- dec. LEA 400kV Tantareni-Kozlodui -> 100-102% TC LEA 400kV Portile de Fier-Djerdap
- dec. LEA 400kV Nis-Sofia V -> 100-102% TC LEA 400kV Portile de Fier-Djerdap
- dec. LEA 400kV Djerdap-Bor -> 100-102% TC LEA 400kV Tantareni-Kozlodui

02-12.04

- dec. LEA 400kV Arad-Mintia -> 100-102% TC LEA 400kV Portile de Fier-Djerdap

23-27.04+40.04

- dec. AT2 220/110kV Timisoara -> 100-105% TC LEA 220kV Timisoara-Sacalaz

Import

- dec. LEA 400kV Rosiori-Gadalin -> 100-102% AT 400/220kV Rosiori